



CITY OF GAHANNA

CLARIFICATION #1

2016 STREET PROGRAM – ST 1039

1. Item 1503 – Cement Stabilization. A mix design shall not be required if the contractor bids an assumed 6% cement content and an assumed soil weight of 110 PCF, which is 59.4 lb/cy. Mill depth will be 12 inches. Cure coat will not be required.
2. Item 307 – 7” Concrete Base. Epoxy coated dowel baskets will not be required at the transverse and longitudinal joints.
3. Bid Item #23 – handicap sign. This is a 644 thermoplastic handicap symbol for pavement, not a sign per spec item 630. Preformed thermoplastic symbols in accordance to 647 may be used in lieu of 644. Handicap symbols must meet all applicable ADA requirements for size and color.
4. Item 644 – No Parking – The letters shall be 12” in height. The contractor may use preformed thermoplastic lettering in accordance to 647 in lieu of 644.
5. The construction of Amesbury should be considered full width, and shall be constructed in full with phases, not part-width construction.
6. Driveway removal as required for the installation of sidewalk within the limits of the sidewalk shall be considered an incidental and part of the excavation necessary for the driveway removal.

Please attach with sealed proposal due on **February 29, 2016 @ 11:00 AM**

CLARIFICATION #1 is hereby acknowledged:

Signature and Title

Company Name

Date

Issued: February 24, 2016